

**Revisions:**

Arkansas


## Arby's - 1632 AR-25 Bypass

Arkansas

Demolition Plan,  
Demolition Notes

DEMO

Date: 10-29-21



Scale:  $1/4" = 1' - 0"$

1. The Demolition Contractor Shall Not Remove Any Structural Load Bearing Walls, Shear Walls, Etc. Without Prior Approval Of The Project Structural Engineer. Verify All Interior Walls Are Non-Load Bearing Or Shear Walls Prior To Removal.
2. The Project Structural Engineer Shall Be Notified Upon Uncovering Of Any Potential structural Framing Prior To Removal. Removal Only Upon Permission Of The Project Structural Engineer.
3. **FIELD VERIFICATION REQUIRED** - The Contractor Shall Advise The Architect & Structural Engineer Of Any Structural Shear Walls That Extend To The Roof Trusses With Plywood Covering And Tie-Down. Remove Only Upon Approval From The Structural Engineer.
4. The Contractor Shall Verify Any Items That Are To Be Retained For The Owner Prior To Removal From The Site.